

PGDP GROUNDWATER HISTORY & ACCOMPLISHMENTS

REMEDIATION

_


2009 C-400 Phase I action remedial action fieldwork commences





2010C-400 Phase I (electrical resistance heating) operations completed 12

2011 C-400 Phase II Remedy Proposals 12





C-400 PHASE I: (DUAL PHASE HEATING) SYSTEM USED TO DESTROY TCE + TCE DNAPL SHALLOW ZONE ABOVE AQUIFER @ C-400 CLEANING FACILITY

C-400 PHASE II: STEAM INJECTION TO DESTROY TCE & TCE DNAPL AT C-400 CLEANING FACILITY

C-400 PHASE II: OXIDANT INJECTION TO DESTROY TCE AT C-400 CLEANING FACILITY

2012 DOE, EPA and KY agree to conduct 2D and 3D numerical modeling to evaluate potential for Steam Injection to remove DNAPL at C-400 Building





ONE INJECTION WELL

Temperature profile after 30 days of steam injection for case rz-13 with Kh= 200 ft/d and 18:1 anisotropy. Steam is injected in the bottom interval in the rga at a rate of 5000 lbs/hr.



ONE INJECTION WELL

Temperature profile after 30 days of steam injection for case RZ-12 with Kh= 200 ft/d and 18:1 anisotropy. Steam is injected in the bottom interval in the rga at a rate of 2000 lbs/hr.



Temperature profile after 30 days of steam injection for case RZ-4 with Kh= 200 ft/d and 18:1 anisotropy. Steam is only injected at two intervals in the rga at 500 lbs/hr in each interval.


ONE INJECTION WELL

Temperature profile after 30 days of steam injection for case RZ-11 with Kh= 200 ft/d and 18:1 anisotropy. Steam is only injected in the bottom interval in the RGA at a rate of 1000 lbs/hr.

200 ft/d

425 ft/d

750 ft/d



3-D QUARTER FIVE-SPOT MODEL USED IN NUMERICAL SIMULATIONS OF STEAM INJECTION (ABOVE AND RIGHT)

COMPARISON OF 3D SIMULATIONS



+









